

AD-A156 424


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAM  
FIRST CONNECTICUT LAKE (U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV MAY 79


1/1

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A


AD-A156 424

CONNECTICUT RIVER BASIN  
PITTSBURG, NEW HAMPSHIRE

**FIRST CONNECTICUT LAKE DAM****NH 00186****NHWRB 194.02**

**PHASE I INSPECTION REPORT**  
**NATIONAL DAM INSPECTION PROGRAM**

Copy available to DTIC does not  
permit fully legible reproduction



DTIC FILE COPY

DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

MAY 1979

**DISTRIBUTION STATEMENT A**

Approved for public release  
Distribution Unlimited

**85 06 14 030**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

AD A 156 424

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00186	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) First Connecticut Lake Dam  NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE May 1979
		13. NUMBER OF PAGES 68
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report)  UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY,  Connecticut River Basin Pittsburg, New Hampshire Connecticut River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  The dam is a concrete gravity dam with earth embankemtns at each end. The dam is considered to be in good condition although the deteriorated cocncrete requires superficial patch work in many places. It is large in size with a low hazard potential.		

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
424 TRAPELO ROAD  
WALTHAM, MASSACHUSETTS 02154

REPLY TO  
ATTENTION OF:  
NEDED

JUN 26 1976

Honorable Hugh J. Gallen  
Governor of the State of New Hampshire  
State House  
Concord, New Hampshire 03301

Dear Governor Gallen:


I am forwarding to you a copy of the First Connecticut Lake Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire. In addition, a copy of the report has also been furnished the owner, New England Power Company, 9 Court Street, Lebanon, New Hampshire 03766.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely yours,

  
JOHN P. CHANDLER  
Colonel, Corps of Engineers  
Division Engineer

Incl  
As stated

FIRST CONNECTICUT LAKE DAM

NH 00186

NHWRB 194.02

CONNECTICUT RIVER BASIN  
PITTSBURG, NEW HAMPSHIRE

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

Accession For		
NTIS GRA&I	<input checked="" type="checkbox"/>	
DTIC TAB	<input type="checkbox"/>	
Unannounced	<input type="checkbox"/>	
Justification		
By		
Distribution/		
Availability Codes		
Dist	Avail and/or	
	Special	
A/1		

NATIONAL DAM INSPECTION PROGRAM  
PHASE I INSPECTION REPORT

Identification No.: NH 00186  
Name of Dam: First Connecticut Lake Dam  
Town: Pittsburgh  
County & State: Coos, New Hampshire  
Stream: Connecticut River  
Date of Inspection: June 28, 1978

BRIEF ASSESSMENT

First Connecticut Lake is located in the northern part of the state on the Connecticut River about 8 miles upstream from the town of Pittsburg, New Hampshire. This is a concrete gravity dam with earth embankments at each end. The mass concrete spillway has a total length of 387 feet and contains two sluice gates and a log way near the southern abutment. The maximum height of the dam is 56 feet, and there are mass concrete abutment walls at the junction of the dikes and the spillway. A footbridge above the spillway crest extends the entire length of the spillway and provides access to the manually operated flashboards as well as to the sluice gates and log way. The south dike is about 480 feet long with maximum height of 22 feet. The north dike is about 250 feet long with a maximum height of 15 feet.

Based on visual inspection, available records, and past operational performance, the dam is considered to be in good condition although the deteriorated concrete requires superficial patch work in many places. Seepage was noted at the junction of the southern abutment and dike. An old slide was observed between the southern abutment and retaining wall. The continuance of this classification depends on proper operations and maintenance of the dam.

This dam falls under the category of low hazard potential, and it is large in size. The test flood peak inflow is equal to the probable maximum flood, 103,500 cfs, and the test flood peak outflow is 15,000 cfs. Hydraulic analysis indicates that the maximum surcharge pool elevation will be 1640, approximately 7 feet below the top of the earth dike. The spillway will pass the test flood peak outflow without overtopping the dam, and therefore the spillway capacity is adequate.

The following recommended operation and maintenance measures, as stated in Section 7.3, should be implemented within two years of the receipt of this Phase I report by the owner:



- (1) Maintenance program of the owner and the technical annual periodic inspection being performed by the owner's engineering staff should be continued.
- (2) Monitoring of the seepage and slide area to determine the cause and then corrective measures should be taken.
- (3) Vegetation should be removed except for grass cover that prevents slope erosion.
- (4) A program should be prepared and initiated to repair the slope protection as it becomes necessary.
- (5) The upstream slope of the dam should be inspected at low water.
- (6) Surveillance should be continued and a warning system should be developed for periods of unusually heavy rains and runoff.
- (7) All deteriorating concrete surfaces should be repaired.

FAY, SPOFFORD & THORNDIKE, INC.

By



*Jurgis Gimbutas*  
Jurgis Gimbutas, P.E.  
Project Engineer

*Richard W. Albrecht*  
Richard W. Albrecht, P.E.  
Vice President

This Phase I Inspection Report on First Connecticut Lake Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.



CHARLES G. TIERSCH, Chairman  
Chief, Foundation and Materials Branch  
Engineering Division




FRED J. RAVENS, Jr., Member  
Chief, Design Branch  
Engineering Division



SAUL COOPER, Member  
Chief, Water Control Branch  
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR  
Chief, Engineering Division

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway test flood is based on the estimated "probable maximum flood" for the region (greatest reasonable possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition, and the downstream damage potential.

# TABLE OF CONTENTS

	<u>Page</u>
Letter of Transmittal	i
Brief Assessment	iii
Review Board Signature Sheet	iv
Preface	v
Table of Contents	viii
Overview Photograph	ix
Location Map	
 REPORT	
 SECTION 1 - PROJECT INFORMATION	 1
1.1 General	1
a. Authority	1
b. Purpose	1
1.2 Description of Project	1
a. Location	1
b. Description of Dam	2
c. Size Classification	2
d. Hazard Classification	3
e. Ownership	3
f. Operator	3
g. Purpose of Dam	3
h. Design and Construction History	3
i. Normal Operational Procedure	5
1.3 Pertinent Data	5
a. Drainage Area	5
b. Discharge at Dam Site	5
c. Elevation (Feet above MSL)	5
d. Reservoir	6
e. Storage (Acre-Feet)	6
f. Reservoir Surface (Acres)	6
g. Dam	7
h. Spillway	7
i. Regulating Outlet	8
 SECTION 2 - ENGINEERING DATA	 9
2.1 Design	9


	<u>Page</u>
2.2 Construction	9
a. Concrete Properties	9
b. Construction History	9
c. Testing	9
2.3 Operation	10
2.4 Evaluation	10
a. Availability	10
b. Adequacy	10
c. Validity	10
SECTION 3 - VISUAL INSPECTION	11
3.1 Findings	11
a. General	11
b. Dikes	11
c. Appurtenant Structures	11
d. Reservoir Area	12
e. Downstream Channel	12
3.2 Evaluation	12
SECTION 4 - OPERATIONAL PROCEDURES	13
4.1 Procedures	13
4.2 Maintenance of Dam	13
4.3 Maintenance of Operating Facilities	13
4.4 Description of any Warning System in Effect	13
4.5 Evaluation	13
SECTION 5 - HYDRAULIC/HYDROLOGIC	14
5.1 Evaluation of Features	14
a. Design Data	14
b. Experience Data	14
c. Visual Observations	14
d. Overtopping Potential	14

	<u>Page</u>
SECTION 6 - STRUCTURAL STABILITY	16
6.1 Evaluation of Structural Stability	16
a. Visual Observations	16
b. Design and Construction Data	16
c. Operating Records	16
d. Post-Construction Changes	16
e. Seismic Stability	16
SECTION 7 - ASSESSMENT, RECOMMENDATIONS, & REMEDIAL MEASURES	17
7.1 Dam Assessment	17
a. Condition	17
b. Adequacy of Information	17
c. Urgency	17
d. Need for Additional Investigation	17
7.2 Recommendations	17
7.3 Remedial Measures	17
7.4 Alternatives	18
APPENDIX A - VISUAL INSPECTION CHECK LISTS	A-1
APPENDIX B - EXISTING AVAILABLE INFORMATION	B-1
APPENDIX C - PHOTOGRAPHS	C-1
APPENDIX D - HYDROLOGIC & HYDRAULIC COMPUTATIONS	D-1
APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS	E-1

OVERVIEW PHOTOGRAPH



FIRST CONNECTICUT LAKE DAM, LOOKING NORTH ON THE DOWNSTREAM SIDE  
Negative No. 10-17




UNITED STATES  
DEPARTMENT OF INTERIOR  
GEOLOGICAL SURVEY

SCALE 1:62500 (ACTUAL)

NEW H  
INDIAN STR  
NEW  
SECOND CONNECT





SCALE 1:62500 (ACTUAL)

NEW HAMPSHIRE-VERMONT  
INDIAN STREAM QUADRANGLE 1926  
NEW HAMPSHIRE-MAINE  
SECOND CONNECTICUT LAKE QUADRANGLE 1927

242

## FIRST CONNECTICUT LAKE DAM

### SECTION 1 - PROJECT INFORMATION

#### 1.1 General

##### a. Authority

Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Fay, Spofford & Thorndike, Inc., have been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed was issued to Fay, Spofford & Thorndike, Inc., under a letter of May 3, 1978, from Mr. Ralph T. Garver, Colonel, Corps of Engineers. Contract No. DACW33-78-C-0308 has been assigned by the Corps of Engineers for this work.

##### b. Purpose

- (1) Perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.
- (2) Encourage and prepare the states to initiate quickly effective dam safety programs for non-federal dams.
- (3) To update, verify, and complete the National Inventory of Dams.

#### 1.2 Description of Project

##### a. Location

First Connecticut Lake is located in the northern part of the state of New Hampshire. The dam is located on the Connecticut River at the western bay of the lake and about eight miles upstream from Pittsburg, New Hampshire. It is within the borders of this township and is adjacent to U.S. Highway Route 3.

## b. Description of Dam

This dam, designed by the New England Power Construction Co., Engineers, Boston, Massachusetts, is a concrete gravity dam with earth dike embankments at each end. The concrete dam is founded on ledge and the embankments on soil. The mass concrete spillway with a total length of 387 feet contains two sluice gates and a log way near the south abutment. The maximum height is 56 feet. There are mass concrete retaining walls where the dikes join the spillway (Photographs No. 6, 7, and 8, Appendix C).

On top of the spillway, there are 4-foot high wooden flashboards having a total length of 358 feet. A large spillway capacity was provided since the spillway section was the most economical type of construction (Photographs No. 1 and 2, Appendix C).

A footbridge with the floor elevation 10 feet above the spillway concrete crest extends the entire length of the spillway and provides access to the manually-operated flashboards as well as to the sluice gates and log way.

Two sluice gates, each 7 feet 8 inches by 9 feet 8 inches, are installed at about the lowest point in the riverbed. Centerlines of the gates are 30 feet below the spillway concrete crest. The gates are operated by an electric motor, which is protected in a wooden gate house. South of the sluice gates, a 10-foot wide log way was provided for the passage of timber logs. The sill of the log way entrance is 14 feet below the spillway concrete crest and is at Elevation 1636.0 msl. The log way is controlled by manually operated stop logs. To guarantee a minimum flow of 8 cfs during the summer, there is a fish pipe near the south gate (Photographs No. 3, 4, and 11, Appendix C).

The dike embankments are of the rolled fill type, constructed on an earth foundation. The top of the embankments is 15 feet wide at Elevation 1647.0. The downstream slope is 1 vertical to 2 horizontal and the upstream 1 vertical to 2.5 horizontal with riprap slope protection. The south dike is about 480 feet long, with a maximum height of 22 feet. The north dike is about 250 feet long, with maximum height of 15 feet (Photographs No. 13 and 14, Appendix C). The total length of both the dikes and the spillway is about 1,120 feet.

## c. Size Classification

The storage capacity at the top of the dam is 114,000 acre-feet which is more than 50,000 acre-feet. Therefore, the dam is classified as large in size according to Table 1, Size Classification,

in the "Recommended Guidelines for Safety Inspection of Dams," furnished by the Corps of Engineers.

d. Hazard Classification

There are no permanent structures for human habitations between the First Connecticut Lake Dam and the downstream Francis Lake Dam. It is estimated that in the event of failure of this dam, minimal property damage would probably occur. Therefore, on the basis of Table 2, Hazard Potential Classification, in the "Recommended Guidelines for Safety Inspection of Dams," furnished by the Corps of Engineers, this dam falls in the category of low hazard potential.

e. Ownership

According to available records, the Upper Connecticut River and Lake Improvement Co. of West Stewartstown, New Hampshire, was the owner in the 1930's. Prior to that, the Connecticut River Power Co. of Boston, Massachusetts, and Connecticut Lakes Conservation Co. of Pittsburg, New Hampshire, were the owners.

After 1939, the dam and the water rights were purchased by the New England Power Co. of Westborough, Massachusetts, with a regional office in Lebanon, New Hampshire.

f. Operator

The dam on the First Connecticut Lake is being operated by New England Power Co. Daily operation of the dam is by Mr. Lindsay L. Covill, supervisor, who resides near the dam on Route 3.

The maintenance engineer is Mr. John E. Whitcomb of the New England Power Co., 9 Court Street, Lebanon, New Hampshire, telephone (603) 448-2200.

g. Purpose of Dam

Originally, the prime purpose of this dam was to regulate the flow of water for log driving. Today, the purpose of the First Connecticut Lake, as well as adjacent lakes, is to store water for release downstream during low flows for industrial use and incidental flood control. This also results in recreational benefits.

h. Design and Construction History

Available records indicate that the oldest dam at the outlet of the First Connecticut Lake was built approximately in the year 1880. It was a typical rock filled timber cribbed structure with a

27-foot long spillway and with a height about 17 to 18 feet. In 1915, this dam was removed and replaced by a new timber cribbed dam with earth dikes at both ends. This dam had a sluiceway for logging with a crest elevation of 1637 msl, which is equal to a head of 25 feet. Due to practical aspects, the dam was operated so that the water level would not exceed Elevation 1633.

In March, 1930, the Connecticut Lakes Conservation Co. filed a statement for a proposed new dam to be constructed about 50 feet below the timber crib dam. Drawings and specifications were prepared, and a new dam was built by the New England Power Construction Co. The new dam increased the water level by 7 feet over the level of the old dam. The construction was started in the spring of 1930, and completed in the summer of 1931. During construction, water was controlled by the old crib dam and diverted from the areas where work was progressing by means of sluices or low cofferdams. The compaction of the earth dikes was accomplished by using 3-wheel rollers weighing not less than 10 tons. The entire upstream slope of the dikes was protected with an 18-inch thick layer of riprap.

The mass concrete was specified to be "dense and impervious" with a minimum ultimate strength of 2,000 psi at 28 days. The main reinforcing was specified to have a 5-inch concrete cover. Concrete was tested in the laboratory of Power Construction and Engineering, Inc., and reviewed by the New Hampshire Public Service Commission. Sand and gravel was obtained from the Merrill Pit. Typical test results indicated the concrete strengths exceeding 3,000 psi at 28 days.

During the summer of 1965, the wingwall of the south abutment was repaired to eliminate cracks and the displacement of construction joints. This pinning repair was designed by the New England Power Service Co.

In 1974, an inspection of this dam by engineers from the New Hampshire Water Resources Board revealed concrete erosion at several places. The structure was proclaimed "to be approaching a state of disrepair." In the following year, the owner undertook repairs of the concrete near the gate house and other areas. In 1975/1976, the backfill at the south abutment was removed and replaced by impervious material to eliminate seepage through the dike. The concrete under the gate house and at the fishscreen was repaired. Substantial repairs on the upstream side were done between November, 1977, and March, 1978. These repairs included refacing the concrete from the south abutment for a distance of 100 feet north of the fishscreen. The owner plans to repair the downstream side within the next three years.

i. Normal Operational Procedure

Mr. Lindsay L. Covill, supervisor, residing adjacent to the dam site, provides round-the-clock surveillance for this dam. He is responsible for the daily inspection, routine maintenance and the regulation of flow. The water level, temperature, and rainfall are recorded daily. Flow rates may be varied at the discretion of the supervisor or at the direction of the owner, New England Power Co.

The dam is inspected yearly by the owner's engineering staff and remedial work performed at their recommendations. The New Hampshire Water Resources Board has inspected this dam at irregular intervals.

1.3 Pertinent Data

a. Drainage Area

First Connecticut Lake is a natural lake and storage in the lake was increased by the construction of the dam across the lake outlet. This dam is about 8 miles upstream of Pittsburg, New Hampshire. The drainage area of First Connecticut Lake is 83 square miles. The watershed area is heavily wooded and of mountainous topography.

b. Discharge at Dam Site

- (1) Outlet works (conduits): One 8-inch diameter pipe with an invert elevation of 1604.0. The estimated discharge through this conduit at Lake Elevation 1640 is 16 cfs. The estimated discharge through the two sluice openings (each 7 feet wide by 9 feet high) with invert elevation at 1601.5 is 3,720 cfs at Lake Elevation 1640.0.
- (2) Maximum known flood at the dam site is unknown.
- (3) The ungated spillway capacity at the maximum design pool elevation 1640.0 is 8,900 cfs.
- (4) The total spillway capacity at the maximum design pool elevation 1640.0 is 15,394 cfs.

c. Elevation (Feet above MSL)

- (1) Top of dam - 1647.0.
- (2) Maximum pool design surcharge - 1640.0. This is an assumed value as the drawings indicate that the normal high water elevation is 1640.0.

- (3) Top of flashboards - 1640.0.
- (4) Spillway crest (top of concrete) - 1636.0.
- (5) Stream bed at centerline of dam - 1590 (estimated).
- (6) Maximum tail water - 1600 (estimated).

d. Reservoir

- (1) Length of maximum pool - 29000 feet (estimated).
- (2) Length of recreation pool - 23760 feet (estimated).
- (3) Length of flood control pool - 25000 feet (estimated).

e. Storage (Acre-Feet)

The following values (above Elevation 1600.0) have been taken from the capacity curve furnished by New England Power Co.:

- (1) Water reservoir at spillway crest elevation - 78,000 acre-feet.
- (2) Design surcharge - unknown.
- (3) Top of dam - 114,000 acre-feet.
- (4) Top of flashboards or normal high water - 91,000 acre-feet.

f. Reservoir Surface (Acres)

The following values have been taken from area-elevation curve furnished by New England Power Co.:

- (1) Top of dam - 3,380 acres.
- (2) Maximum pool - 3,140 acres.
- (3) Flood-control pool - not applicable.
- (4) Spillway crest - 2,980 acres.

g. Dam

- |                             |  |
|-----------------------------|--|
| (1) Type                    | Concrete spillway with earth embankments (dikes) at either end.                          |
| (2) Length                  | 1,117 feet.  |
| (3) Height                  | Maximum 56 feet.   |
| (4) Top width of embankment | 15 feet.   |
| (5) Embankment slopes       |  |
| (a) Upstream                | 1 vertical to 2.5 horizontal.  |
| (b) Downstream              | 1 vertical to 2 horizontal.  |
| (6) Zoning                  | Dikes are homogenous consisting of selected local material (boulder clay or rock flour). |
| (7) Impervious core         | None.  |
| (8) Cutoff                  | Cut-off trench at the centerline of dike when necessary.                                 |
| (9) Grout curtain           | None.  |

h. Spillway

- |                       |                                 |
|-----------------------|---------------------------------|
| (1) Type              | Ogee shaped weir.               |
| (2) Length of weir    | 358 feet (net length).          |
| (3) Crest elevation   | 1636 msl.                       |
| (4) Control mechanism | Flashboards, manually operated. |
| (5) U/S channel       | Lake.                           |



i. Regulating Outlet

- (1) Two 7-foot by 9-foot concrete sluice conduits
  - (a) Invert 1601.5 msl.
  - (b) Control mechanism Two gates, operated by an electric motor with a gasoline motor and manual backup.
- (2) 10-foot wide log way
  - (a) Invert 1622.0 msl.
  - (b) Control mechanism Stop logs, manually operated.
- (3) 8-inch steel pipe
  - (a) Invert 1604.0 msl.
  - (b) Control mechanism Gate valve.

## SECTION 2 - ENGINEERING DATA

### 2.1 Design

Specifications and a geology report dated 1930 was obtained from project records. Drawings indicating plans, elevations and sections of the dam, appurtenant structures and outlet works were obtained from the New England Power Co. Selected drawings are included in Appendix B, following the listing of records and past inspection reports. Discharge rating curve of the spillway and the sluices was also obtained from New England Power Co. These curves are furnished in Appendix D.

### 2.2 Construction

#### a. Concrete Properties

The plans specified an ultimate strength of at least 2,000 psi at the end of 28 days. The concrete used developed a strength exceeding 3,000 psi in 28 days. The aggregate was obtained from Merrill Pit. The laboratory report on the concrete indicated the following:

Design mix - 1 cement: 2.2 sand: 3.5 aggregate  
Slump - 3 3/4"  
Cement Brand - Dragon

#### b. Construction History

- (1) During construction, water was controlled by the old dam and diverted from the area where work was progressing by means of sluices or low cofferdams.
- (2) Construction sequence, pertinent construction problems, and alterations are not available from project records.
- (3) Modifications and maintenance repairs are available from project records and described in Section 1.2(h).

#### c. Testing

Concrete testing was performed by the Power Construction and Engineering, Inc., and reviewed by the New Hampshire Service Commission. The cement was tested by E. L. Conwell and Co., Philadelphia, Pennsylvania. Soil samples were sent to the New Hampshire Department Laboratory for analysis. See Appendix B for listing of data related to testing of materials.

### 2.3 Operation

The water in the lake is checked daily and the level recorded along with temperature and rainfall. There is a U.S.G.S. stream gaging station one-fourth mile downstream of the dam. During floods, the engineers of the New England Power Co. communicate with the Corps of Engineers.

### 2.4 Evaluation

#### a. Availability

Pertinent structural, geotechnical, hydrologic, and hydraulic data, which formed the basis of the design of the dam, are available to a limited extent from the project records.

#### b. Adequacy

Sufficient engineering data are available for a Phase I inspection.

#### c. Validity

The available engineering data is considered valid on the basis of the results of the visual inspection.

## SECTION 3 - VISUAL INSPECTION

### 3.1 Findings

#### a. General

The Phase I inspection of First Connecticut Lake was performed on June 28, 1978. A copy of the inspection check list is included in Appendix A.

In general, the soil and rock features are in good condition. Generally, the upstream side of the concrete structures was observed to be in good condition but the downstream side to be in poor condition, see subparagraph c.

#### b. Dikes

The dikes on either side of the concrete spillway are in good condition. No evidence of vertical or horizontal misalignments was observed nor was there any evidence of piping. The upstream rip-rap slope protection is generally in fair condition, and there is no indication of sloughing, bulging, or movement of the slope.

Vegetation, consisting of weeds and grass, was noted on both the upstream and downstream slopes.

There is an area between the southern abutment and southern spillway wall where the slope has failed. Seepage, minor in nature, was also observed in this area. This area is protected by the spillway wall and the abutment, both of which are founded on bedrock. It appears that this slope failure occurred years ago and the grass has reestablished. This was also observed by the Water Resource Board in 1976 and it is being monitored by the owner, New England Power Co.

Seepage, minor in nature, was observed at the junction of the southern abutment and dike.

Water was observed seeping from the south abutment. It appears to be leaking from a cold joint at approximately Elevation 1638.

#### c. Appurtenant Structures

All concrete on the upstream side above the water line was observed to be in good condition except for the north abutment. The

concrete surface of the north abutment was observed to be in poor condition with several badly spalled areas. In general, the concrete surface on the downstream side is in poor condition with numerous badly spalled areas. Joint alignment is generally good and no cavitation was noted. Efflorescence was noted on both the upstream and downstream sides of both abutments and the south retaining wall.

Field observations indicate that the wooden gate house is well maintained and houses the gate operating equipment. This equipment was observed to be in good condition. The concrete piers of the gate house are also in good condition.

The wooden footbridge, the steel piers, and railing located over the spillway are in good condition. The flashboards and the manually operable stop logs were observed to be in good condition.

#### d. Reservoir Area

First Connecticut Lake is a natural one. Due to the construction of the dam, the storage in the lake is increased. The lake area at the top of the dam is 3,380 acres. The lake is surrounded by forest and mountains.

#### e. Downstream Channel

The downstream channel and side slopes are in good condition.

### 3.2 Evaluation

The observed condition of the dam is good. The potential problems observed during the visual inspection are:

a. The poor condition of the concrete surface on the downstream face of the spillway and the north abutment.

b. Seepage at the junction of the southern abutment and dike.

c. The area between the southern abutment and southern spillway wall where the slope has failed.

## SECTION 4 - OPERATIONAL PROCEDURES

### 4.1 Procedures

The New England Power Co. has operated the First Connecticut Lake Dam since 1939. The lake level is maintained by the spillway and the log way. The flow is controlled manually by flashboards at the spillway and stop logs at the log way. There is an 8-inch diameter pipe for maintaining minimum discharge. Drawdown is accomplished by the opening of two sluice gates which are operated by electric motors. For more details, see Section 1.2.i.

### 4.2 Maintenance of Dam

The maintenance of First Connecticut Lake Dam is the responsibility of the New England Power Co. The upstream face of the dam has been repaired in stages during the last three years. There are plans to repair the downstream face during the next few years.

### 4.3 Maintenance of Operating Facilities

The dam is inspected yearly by the owner's engineering staff and daily by the owner's supervisor, residing near the dam site.

Maintenance of the facilities to operate the gates controlling the flow in the two sluices is good.

### 4.4 Description of any Warning System in Effect

A flood warning system is non-existent, but the supervisor who resides near the dam keep a close watch during floods. He has both telephone and radio communications with the Lebanon, New Hampshire office.

### 4.5 Evaluation

The freeboard for the earth embankment during the test flood inflow is satisfactory. The operational and maintenance procedure consisting of daily and yearly inspections should ensure that all problems encountered can be remedied within a reasonable period of time.

## SECTION 5 - HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

#### a. Design Data

- (1) This dam falls under the category of low hazard potential, and it is large in size. Using the "Recommended Guidelines for Safety Inspection of Dams," the recommended spillway test flood peak inflow equals the probable maximum flood. The spillway test flood peak inflow was determined to be approximately 103,500 cfs. The spillway test flood inflow hydrograph is furnished in Appendix D.
- (2) The estimated peak outflow is 15,000 cfs, obtained as a result of flood routing. See Appendix D for details.
- (3) The reservoir storage capacity versus the elevation curve is furnished in Appendix D.
- (4) The estimated composite rating curve for the spillway and all discharging facilities is furnished in Appendix D.
- (5) The hydrologic map of the watershed above the dam site, including reservoir area and watercourse, is furnished in Appendix D.

#### b. Experience Data

There is no evidence of the magnitude of floods and resulting maximum peak inflows in the past.

#### c. Visual Observations

The valley cross section immediately below the dam is sufficient to convey the peak outflow of 15,000 cfs from the lake. The valley section is rocky and the flow over the spillway is allowed to fall freely onto the downstream channel bed. Noticeable scour of the channel bed was not detected.

#### d. Overtopping Potential

For conservative analysis, the spillway test flood peak inflow has been taken to be equal to 103,500 cfs that can result from the total drainage area above the First Connecticut Lake Dam. The

maximum surcharge pool elevation in the First Connecticut Lake, when the spillway test flood inflow hydrograph has been routed through the lake, is 1640.0. The available freeboard is 7 feet as the top of the earth dam is at Elevation 1647.0. Therefore, the First Connecticut Lake Dam will not be overtopped when the spillway test flood inflow hydrograph passes through the lake if all the discharge facilities are maintained to function at their optimum capacity.

Currently, a report on the detailed hydrologic studies of this lake is being prepared by Chas. T. Main, Inc., and it is expected that it will be available in the latter part of 1978. Our conclusions pertaining to overtopping should be subject to revision depending on the spillway test flood inflow hydrograph evaluated by Chas. T. Main, Inc.



## SECTION 6 - STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

#### a. Visual Observations

The upstream slope could not be seen due to the fact that it was underwater. The slopes of the embankment do not show any erosion or other weak areas. The visual inspection revealed no evidence of stability problem except possibly for the seepage at the junction of the southern abutment and dike.

#### b. Design and Construction Data

Design drawings and specifications were obtained from the project records. No design computations were available but the magnitude of the uplift pressure used is available from the project records. The main section of the dam is the mass concrete spillway which is founded on ledge. It was designed with an allowance for uplift on the base varying from two-thirds of the full hydrostatic pressure at the upstream heel to zero pressure at the downstream toe. The resultant was held within the middle third.

#### c. Operating Records

Except for a few records, which are listed in Appendix B, other operating records are available at the office of the New England Power Co.

#### d. Post-Construction Changes

Presumably, the last improvements were done in March, 1978.

#### e. Seismic Stability

The dam is located in Seismic Zone 2 and in accordance with recommended Phase I guidelines does not warrant seismic analyses.

## SECTION 7 - ASSESSMENT, RECOMMENDATIONS, & REMEDIAL MEASURES

### 7.1 Dam Assessment

#### a. Condition

Examination of available documents and visual inspection of the First Connecticut Lake Dam and its appurtenant structures did not reveal any defects which would render the project inadequate from the standpoint of structural stability and the dam is judged to be in good condition.

#### b. Adequacy of Information

An adequate assessment of the dam consistent with the scope of a Phase I investigation has been made based upon the visual inspection and available information.

#### c. Urgency

The operational and maintenance measures enumerated in Section 7.3 below should be implemented within two years of receipt of this report by the owner.

#### d. Need for Additional Investigation

The information available from the visual inspection is adequate to identify the potential problems which are: seepage and the old slide between the southern abutment and spillway retaining wall. These problems require the monitoring by the engineering staff of the owner to determine the cause and then specify remedial measures to rectify the problem.

### 7.2 Recommendations

No major modification or engineering investigation is recommended at this time.

### 7.3 Remedial Measures

Although the dam is generally maintained in good condition, it is considered important that the following operating and maintenance procedures be accomplished:

- a. The maintenance program of the owner should be continued.

b. All concrete surfaces should be repaired as continued deterioration could develop a serious problem.

- (1) Considerable erosion and spalling of the concrete was noticed on the downstream face of the spillway, the north abutment, and the two piers of the gate house.
- (2) The wingwall adjacent to the log way is in poor condition especially at the lower elevations. Efflorescence also was observed.
- (3) In the two bays where the sluice gates are located, there is considerable erosion and spalling of concrete of the spillway from the crest to the toe.

c. Seepage was observed at the junction of the southern abutment and dike. This area should be monitored to determine the cause and corrective measures should be taken.

d. The monitoring of the area between the southern abutment and spillway retaining wall, which previously failed, should be continued by the New England Power Co. As soon as the cause is determined, corrective measures should be undertaken.

e. Vegetation should be removed from the dam embankment except for grass cover that prevents slope erosion.

f. A program should be prepared and initiated to repair the slope protection as it becomes necessary.

g. Upstream slope of dam should be inspected at low water.

h. Round-the-clock surveillance should be continued during periods of high precipitation.

i. The owner should develop a formal warning system. An operational procedure integrated with the operational procedure of Francis Lake to follow in the event of an emergency should be adopted.

#### 7.4 Alternatives

None recommended.

APPENDIX A  
VISUAL INSPECTION CHECK LISTS

# APPENDIX A

## VISUAL INSPECTION CHECK LIST PARTY ORGANIZATION

PROJECT First Connecticut Lake Dam      DATE June 28, 1978  
 TIME 900 - 1100, 1400 - 1700  
 WEATHER Drizzle, Sunny in Afternoon  
 W.S. ELEV. 1638.0 U.S. \_\_\_\_\_ DN.S. \_\_\_\_\_

### PARTY:

1. <u>Jurgis Gimbutas, P.E.</u>	<u>Team Captain - Structural and Concrete</u>
2. <u>Harvey H. Stoller, P.E.</u>	<u>Soils, Geology, &amp; Foundations</u>
3. <u>V. Rao Maddineni, P.E.</u>	<u>Hydraulics &amp; Hydrology</u>

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Dike Embankment</u>	<u>H. H. Stoller</u>	<u>Good</u>
2. <u>Log Way</u>	<u>J. Gimbutas</u>	<u>Good</u>
3. <u>Gate House</u>	<u>J. Gimbutas</u>	<u>Good</u>
4. <u>Outlet Works - Sluice</u>		
4. <u>Conduit and Fish Pipe</u>	<u>J. Gimbutas</u>	<u>Good</u>
5. <u>Spillway Weir</u>	<u>J. Gimbutas</u>	<u>Poor</u>
6. <u>Approach and</u>	<u>V. R. Maddineni</u>	
6. <u>Discharge Channels</u>	<u>H. H. Stoller</u>	<u>Good</u>
7. <u>Footbridge</u>	<u>J. Gimbutas</u>	<u>Good</u>
8. <u>Lake and</u>		
8. <u>Downstream Channel</u>	<u>V. R. Maddineni</u>	<u>Good</u>

# PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978

PROJECT FEATURE Dike Embankment

DISCIPLINE Soils & Foundations NAME \_\_\_\_\_

PROJECT FEATURE \_\_\_\_\_

DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED

CONDITION

## DIKE EMBANKMENT

Crest Elevation	1647.0 msl
Current Pool Elevation	1638.0 msl
Maximum Impoundment to Date	1640.0 msl
Surface Cracks	None observed
Pavement Condition	None
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	No visual vertical misalignment observed
Horizontal Alignment	No visual horizontal misalignment observed
Condition at Abutment and at Concrete Structures	Normal

# PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978

PROJECT FEATURE Dike Embankment

DISCIPLINE Soils & Foundations

NAME Harry H. Stille

PROJECT FEATURE \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
Indications of Movement of Structural Items on Slopes	None observed
Trespassing on Slopes	None apparent
Sloughing or Erosion of Slopes or Abutments	None observed
Rock Slope Protection - Riprap Failures	Fair condition
Unusual Movement or Cracking at or Near Toes	None observed
Unusual Embankment or Downstream Seepage	South abutment (see Section 3)
Piping or Boils	None observed
Foundation Drainage Features	None observed
Toe Drains	None
Instrumentation System	None

PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978

PROJECT FEATURE Log Way

DISCIPLINE Structures & Concrete

NAME W. J. Sullivan

PROJECT FEATURE \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED

CONDITION

OUTLET WORKS - LOG WAY

- a. Intake Structure -  
Log Way

Condition of Concrete

Good

Stop Logs and Slots

Very good



# PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978

PROJECT FEATURE Gate House

DISCIPLINE Structures

NAME John J. Smith

PROJECT FEATURE \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED

CONDITION

## OUTLET WORKS - GATE HOUSE

### a. Structural

General Condition

Good (wood structure)

Leaks in Gate Chamber

South gate, minor in nature

### b. Mechanical and Electrical

Air Vents

None

Float Wells

None

Crane Hoist

Appears to be in good condition

Elevator

None

Hydraulic System

None

Service Gates

Two gates, operated by an electric motor

Emergency Gates

None

# PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978

PROJECT FEATURE Gate House

DISCIPLINE Structures

NAME

PROJECT FEATURE

DISCIPLINE

NAME

DISCIPLINE

NAME

AREA EVALUATED	CONDITION
----------------	-----------

Lightning Protection  
System

None

Emergency Power  
System

Gasoline motor and manually  
operated

Wiring and Lighting  
System

Operating condition

# PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978  
 PROJECT FEATURE Outlet Works  
 DISCIPLINE Structures & Concrete NAME John J. Smith  
 PROJECT FEATURE \_\_\_\_\_  
 DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_  
 DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED

CONDITION

## OUTLET WORKS - SLUICE CONDUIT

General Condition of Concrete	Good
Erosion or Cavitation	None observed
Outlet Works - Fish Pipe	
Size	8-inch diameter steel pipe
General Condition	Good
Gates	One gate valve, manually operated

# PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978  
 PROJECT FEATURE Spillway Weir  
 DISCIPLINE Structures & Concrete NAME James S.  
 PROJECT FEATURE Approach Channel  
 DISCIPLINE Soils & Foundations NAME   
 DISCIPLINE Hydraulics & Hydrology NAME

AREA EVALUATED	CONDITION
----------------	-----------

## OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS

### a. Approach Channel

General Condition	Good
Loose Rock Overhanging Channel	None observed
Trees Overhanging Channel	None observed
Floor of Approach Channel	Could not be observed

### b. Spillway Weir

General Condition of Concrete	Poor
Rust or Staining	Minor staining
Spalling	Badly spalled areas on the downstream side

# PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978

PROJECT FEATURE Spillway Weir

DISCIPLINE Structures & Concrete

NAME \_\_\_\_\_

PROJECT FEATURE Discharge Channel

DISCIPLINE Soils & Foundations

NAME \_\_\_\_\_

DISCIPLINE Hydraulics & Hydrology

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
----------------	-----------

Any Visible  
Reinforcing

None observed

Any Seepage or  
Efflorescence

Efflorescence at abutments

Drain Holes

None observed

## c. Discharge Channel

General Condition

Good

Loose Rock  
Overhanging Channel

None observed

Trees Overhanging  
Channel

In places

Floor of Channel

Good condition

Other Obstructions

None

# PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978  
 PROJECT FEATURE Footbridge  
 DISCIPLINE Structures & Concrete NAME \_\_\_\_\_  
 PROJECT FEATURE \_\_\_\_\_  
 DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_  
 DISCIPLINE \_\_\_\_\_ NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
----------------	-----------

## OUTLET WORKS - FOOTBRIDGE

### b. Superstructure

Bearings	None
Anchor Bolts	Good condition
Bridge Seat	Good condition, grout pad
Longitudinal Members	Good condition
Underside of Deck	Good condition
Secondary Bracing	Good condition
Deck	Sound, creosoted wood planking
Drainage System	Good condition
Railings	Good condition
Expansion Joints	None
Paint	Good condition

# PERIODIC INSPECTION CHECK LIST

PROJECT First Connecticut Lake Dam DATE June 28, 1978

PROJECT FEATURE Footbridge

DISCIPLINE Structures & Concrete

NAME                     

PROJECT FEATURE                     

DISCIPLINE                     

NAME                     

DISCIPLINE                     

NAME                     

AREA EVALUATED	CONDITION
----------------	-----------

## b. Abutment and Piers

General Condition of Concrete	Poor
Alignment of Abutment	Good
Approach to Bridge	Good

APPENDIX B  
EXISTING AVAILABLE INFORMATION



## APPENDIX B

### 1. Listing of Design, Construction and Maintenance Records

In the files of the New Hampshire Water Resources Board in Concord, New Hampshire, there are drawings and seven folders of engineering and maintenance data regarding the First Connecticut Lake Dam in the town of Pittsburg, New Hampshire, dated from 1915 to 1976, and labeled under Town/Dam No. 194.02.

The following is the summary of the seven folders of records.

- ( 1 ) August 9, 1915 to July 18, 1916. Construction specifications, five drawings (reduced to 11 inches by 24 inches) and correspondence regarding construction of a dam at the outlet of the First Connecticut Lake on the site of an older dam which has been removed.
- ( 2 ) June 28, to September 12, 1917. Letters and testimony regarding flood and operation of flood gates of the dam last winter.
- ( 3 ) June, 1922. Pond gage readings 1919 to 1922, February to April; and sketch showing elevations of overflow, compiled by Mr. B. H. Moxon, from data by Mr. H. G. Philbrook.
- ( 4 ) June 12, to October 13, 1923. Several memorandums and letters regarding the inspections and recommendations for addition of height and other improvements of the dam by: Mr. J. H. Manning of Stone & Webster; Mr. E. W. Philbrook of Upper Connecticut River and Lake Improvement Co.; Mr. S. N. Bigelow of New Hampshire Public Service Commission; I. W. Jones & Co., Engineers, Nielson, New Hampshire.
- ( 5 ) March 20, 1930. Statement of Connecticut Lakes Conservation Co. of a proposed dam reconstruction, filed with plans and specifications. Filed with the New Hampshire Public Service Commission.
- ( 6 ) April 26, 1930. Revised general specifications for a new storage dam at First Connecticut Lake, by New England Power Construction Co., Engineers, Boston, Massachusetts (four pages and an 8 1/2-inch by 11-inch map).
- ( 7 ) May, 1930. Geological Report on the First Connecticut Lake Dam by Mr. Irving B. Crosby, Geologist (eight pages and a map).

- ( 8) 1928-1933. Some fifty large photographs showing the dam before, during, and after construction in 1930.
- ( 9) No date, probably in 1930. Specifications for Rolled Earth Dikes, First Connecticut Lake Storage Dam (seven pages).
- (10) May 17, and 18, 1930. Reports on inspection of dam site by Mr. J. W. Golothwart (two pages).
- (11) Summer, 1930. Many memorandums and letters regarding construction of new dam, including reports on soil samples by New Hampshire Highway Department Laboratory.
- (12) August 10, 1930, and many other dates. Laboratory reports on concrete by Power Construction and Engineering, Inc. Also reports on tests of cement by E. L. Conwell & Co., Philadelphia, Pennsylvania.
- (13) July 26, 1932. Approximate discharge rating of 9-foot by 7-foot sluices and an 8-inch diameter fish pipe, and capacity curve.
- (14) July 5, 1945. Daily and monthly discharges for 1931-1939, and revised station description with basic hydrological data.
- (15) May 4, 1959. Memorandum on the lake levels, addressed to the Governor of New Hampshire, by Mr. W. G. White, Chairman, New Hampshire Water Resources Board (four pages, including tabulation of water levels for 1954 to 1958).
- (16) June 28, 1965. A description of repairs made to the upstream portion of the south abutment wingwall by Mr. A. T. Simmonds, Superintendent, North Division, New England Power Co., Littleton, New Hampshire, to Mr. W. G. White, Chairman, New Hampshire Water Resources Board, with a print of Drawing No. 6171.
- (17) August 16, 1971. A letter explaining minimum discharges of this and other related lakes by Mr. Francis C. Moore, Water Resources Engineer.
- (18) July 7, to November 3, 1976. Several letters and memorandums regarding repair of leakage on the east end of the dam between the New Hampshire Water Resources Board and the New England Power Co.
- (19) January 31, 1975. FIA Hazard Boundary Maps, town of Pittsburg, New Hampshire (Coos Co.) by the Department of

Housing and Urban Development (fifteen pages, 11 inches by 17 inches).

In the files of the New England Power Co., Engineering Department, Westborough, Massachusetts, there are records which we have not seen, but we did receive the following hydrological data:

- (1) Area capacity curves, dated October 18, 1929.
- (2) Spillway discharge rating curve, dated May 18, 1934.
- (3) Discharge rating curve of one of two sluices, dated February 11, 1947 (two pages).
- (4) Storage tables, dated February 10, 1956 (six pages).

## 2. Past Inspection Reports

The New Hampshire Water Resources Board has numerous inspection reports from the years prior to reconstruction of the dam in 1930. Only three representative reports from those years are included here and all four available reports from later years.

- (1) July 26, 1920. By Mr. E. W. Philbrook of Upper Connecticut River and Lake Improvement Co., West Stewartstown, New Hampshire.
- (2) September 14, 1923. By Mr. S. N. Bigelow, Engineer, of New Hampshire Public Service Commission.
- (3) June 18, 1927. By Mr. A. C. Newhall of UCRLI Co.
- (4) April 28, 1939. By C.S.W. of New Hampshire Water Control Commission.
- (5) October 23, 1974. By Mr. F. C. Moore and Mr. D. M. Rapoza, Engineers, New Hampshire Water Resources Board.
- (6) November 22, 1974. By Mr. S. C. Burritt, Civil Engineer, New Hampshire Water Resources Board.
- (7) April 2, 1976. By Mr. S. C. Burritt, Civil Engineer, New Hampshire Water Resources Board (two pages).

The New England Power Co., Engineering Department, in Westborough, Massachusetts, has more inspection reports for internal use only.

### 3. Drawings

The New Hampshire Water Resources Board is in possession of the following blueprints of drawings that were made by the New England Power Construction Co., Engineers and Contractors, Boston, Massachusetts, for the Connecticut Lakes Conservation Company. General title of all drawings is: First Connecticut Lake Storage.

\*Drawing No. H-4462-0 - Main Dam - Plan & Sections, Dated April 14, 1930.

Drawing No. H-4463-0 - South Bay Dike - Plan & Sections, Dated April 14, 1930.

Drawing No. H-4507 - Plan Showing Lands & Rights Around First Connecticut Lake, Dated April 24, 1930.

Drawing No. H-4540-1 - Main Dam Abutments, Concrete - Plan, Elevations & Sections, Dated May 10, 1930.

Drawing No. H-4552-3 - Main Dam Spillway, Structural, Concrete - Plan, Elevations & Sections, Dated May 13, 1930.

Drawing No. D-6171 - Main Dam, South Abutment, Repairs to Wing-wall, Dated May, 1965.

New England Power Co., Engineering Department, at Westborough, Massachusetts, have original tracing of drawings, three of which copies are included with this report.

- (1) H-4549 - May 15, 1930, Revised September 19, 1930, Main Dam, General Layout (and Sections).
- (2) H-4540 - May 10, 1930, Revised September 18, 1930, Main Dam, Abutments, Concrete, Plan, Elevations, and Sections.
- (3) H-4552 - Main Dam Spillway, Structural Concrete, Plan, Elevation, and Sections.

\*Also included with this report

C O P Y

W. Stewartstown, N.H.  
July 26, 1920

To the Public Service Commission of New Hampshire:

In accordance with instructions in your letter of July 31, 1916, we have inspected the dam at the outlet of First Connecticut Lake in Pittsburg, N.H. and report the following:

- 1- Gravel wings embankments in good shape having been topped out with one foot of gravel in the year 1919. Both wings almost completely grassed over thereby eliminating the danger of washing.
- 2- Bulk head, timber crib work and building over the same in good condition.
- 3- Gates in good operating condition, and reasonably tight.
- 4- All worn sluice ways replaced in 1919 and in good condition at present.
- 5- In the spring of 1920 a small leak was discovered under the 20 foot gate between the timber toe piling and the ledge. This leak was stopped by placing 225 bags of sand in front. When the water in the Lake is low enough an inspection will be made at this particular point, and if considered advisable, a mixture of concrete will be put in.

On the whole we consider the dam in very good condition and would at any time be pleased to have an inspection made by the Public Service Commission of New Hampshire, the expense of so doing to be borne by this Company.

UPPER CONNECTICUT RIVER & LAKE IMPROVEMENT CO.

By (Signed) E. W. Philbrook.

Original letter sent downstairs August 3, 1920, with letter to Mr. Timm.

## NEW HAMPSHIRE

8-1397  
CONCORD September 14, 1923.

Public Service Commission,  
Concord, New Hampshire.

Dear Sirs:-

Herewith I submit my report on the inspection of the dam at First Connecticut Lake owned by the Upper Connecticut River & Lake Improvement Company for the proposed raising of three feet.

I gave particular attention to the timber core of the present dam. Three test pits were dug at the following points; one 100 feet south of the gatehouse, one 75 feet north of the gatehouse, and the other at a point 180 feet north of the gatehouse. The pits were dug to about a five-foot depth from the top of the core. In all cases the top was decayed to a maximum depth of a foot and a half, and from there down the core was sound.

Starting at a point 200 feet north of the north end of the gatehouse and continuing to a point where finished grade hits natural ground, the piling is to be driven to bed rock. The embankment on this stretch has a maximum depth of seven feet. On this stretch something additional will have to be done as one of the company's buildings, as well as the highway, interferes with a two to one slope.

The sod has all been stripped from the downstream face of the dam. Also, sod is removed to a point where the toe of a two to one slope will hit. As yet, the upstream face has not been touched, but this will be stripped to elevation 1220 which will be ten feet, as the new grade for the crest of the dam is elevation 1230. This ten feet area is to be riprapped.

The borrow pit which they are using on the south wing of the dam is good material for fill, having enough clay to bind the coarser material. The pit was one used when the dam was built. For the fill on the north wing they will use another pit which was used at the time the dam was built and is the same material.

At the north end of the gatehouse on the downstream face a crib or a bulkhead is to be built to keep the fill from sliding into the river.

Respectfully submitted,



Engineer.

B-6

LWB:HVV

JUN 27 1927

REPORT ON INSPECTION OF FIRST LAKE DAM, PITTSBURG, N.H.

EARTH EMBANKMENTS

The earth embankments at each end of the crib dam have a minimum width of about 9 feet and have thoroughly settled and compacted to a top elevation of at least 1230'.

At the Northerly end of the crib dam, on both the up-stream and down-stream slopes, there is still a little sloughing off of the fill.

The stones used in riprapping the up-stream slope are now well in place.

The 3" Kyanized spruce plank sheeting is in as good condition as when first placed in 1923.

CRIB DAM

The crib work Easterly of a longitudinal section through the 20', 8' and 6' gates contains timber which has deteriorated more or less since the alterations of 1923; Westerly of this section the timber is in a very good state of preservation.

The top of the present crib work shows more or less settling.

The 3" Kyanized spruce plank used for deck planking are in very good condition.

SOUTH BAY DYKE

South Bay Dyke has grassed over to withstand erosion from wave action.

*Oliver C. Farrell*

June 18, 1927

NEW HAMPSHIRE WATER CONTROL COMMISSION  
DATA ON DAMS IN NEW HAMPSHIRE

LOCATION

STATE NO 124.02

Town Pittsburg : County Cochs  
Stream Connecticut (outlet first)  
Basin-Primary Connecticut : Secondary Connecticut Lake  
Local Name  
Coordinates—Lat. 45° 5' + 2000 : Long. 71° 15' + 10000

GENERAL DATA

81.4 PSC

Drainage area: Controlled.....Sq. Mi.: Uncontrolled.....Sq. Mi.: Total 32.2 Sq. Mi.  
Overall length of dam 200 ft.: Date of Construction  
Height: Stream bed to highest elev. 37 ft.: Max. Structure ft.  
Cost—Dam : Reservoir

DESCRIPTION

Timber Crib, (Rock Filled) *Now earth & concrete dam  
earth dike at South Bay*

Waste Gates

Type  
Number : Size ft. high x ft. wid  
Elevation Invert : Total Area sq. ft.  
Hoist

Waste Gates Conduit

Number : Materials  
Size 2-6 5/8 ft.: Length ft.: Area 120 sq. ft.

Embankment

Type Concrete  
Height—Max. ft.: Min. ft.  
Top—Width : Elev. ft.  
Slopes—Upstream on : Downstream on  
Length—Right of Spillway : Left of Spillway

Spillway

Materials of Construction  
Length—Total 338' ± 10' ft.: Net ft.  
Height of permanent section—Max. 4' ± 12' ft.: Min. ft.  
Flashboards—Type : Height ft.  
Elevation—Permanent Crest : Top of Flashboard  
Flood Capacity cfs.: cfs/sq. mi.

Abutments

Materials:  
Freeboard: Max. ft.: Min. ft.

Headworks to Power Devel.—(See "Data on Power Development")

OWNER Upper Connecticut R. & the Imp. Co.

REMARKS Primary H.P. 2000 time 44

B-8

4/28/1939

Tabulation By 755 Date April 19, 1939



File

M E M O R A N D U M

DATE: October 23, 1974

FROM: Francis C. Moore and Donald M. Rapoza, Engineers

SUBJECT: First Connecticut Lake Dam Inspection - #194.02, Pittsburg

TO: Vernon A. Knowlton, Chief Water Resources Engineer

On October 11, 1974, Francis C. Moore and Donald M. Rapoza inspected First Connecticut Lake Dam in part with New England Power Company Dam Operator Lindsay Covill. The following deficiencies were noted:

1. Piers at gate house were badly eroded.
2. Concrete at gate section was badly eroded, especially on upstream face.
3. Downstream face of dam at gate house had some erosion.
4. Along riverside face of downstream left abutment there was some seepage which apparently was carrying sediment. In June, it is recommended to inspect this seepage to see how a high lake level affects seepage and sediment carrying capacity.
5. Left abutment upstream appears to be satisfactorily stabilized after pinning repairs were made a few years ago.
6. Left dike should be inspected for seepage in June (at full pond). Also check amount of leakage at what Lindsay Covill says is his salt-lick for deer on the left embankment slope downstream.
7. Suggest further inspection of upstream concrete in late fall 1974 when lake is down more than in October to get a better idea of the extent of concrete erosion and its effect on safety of the dam. New England Power Co. engineers should accompany WRB engineers on this inspection.
8. Notify N.E. Power Co. that a periodic inspection of the dam shows it to be approaching a state of disrepair, and what are their plans to repair it.

fcm/js

MEMORANDUM

DATE: November 22, 1974

FROM: Stephen C. Burritt, Civil Engineer

SUBJECT: First Connecticut Lake Inspection in Pittsburg - #194.02 *6/12*

TO: Vernon A. Knowlton, Chief Water Resources Engineer

On November 19, 1974, Don Rapoza and I inspected the First Connecticut Lake Dam with Charles Harrington and Denton Nichols from New England Power System. This was a follow-up to an inspection by Don Rapoza and Francis Moore made in the fall. We inspected this dam as a follow-up to the earlier inspection when there was a report of cracked and eroded concrete on the upstream side near the gate house.

We were unable to see any additional area, as the lake had not been drawn down. Harrington said that the best time was the spring drawdown, and that he would notify us. He is also sending us a list of all of their dams that are under the supervision of the Federal Power Commission, and he is sending us any extra copies of the inspection reports of all of these dams.

scb/js

TO: Vernon A. Knowlton, Chief Water Resources Engineer

FROM: Stephen C. Burritt, <sup>cc</sup> Civil Engineer

SUBJECT: Inspection of 1st & 2nd Conn. Lakes - Pittsburgh <sup>File</sup> (194.02 & 194.07)

Date : April 2, 1976

On April 1st, I inspected the dams at 1st & 2nd Conn. Lakes. With me on the inspection were two members of the New England Power engineering staff, one member of their construction staff, and three members of their operating staff.

2nd Lake:

This dam appears to be in good shape. The only thing that would need any work is the southern (left side) bridge pier. This has a small section of concrete that is deteriorating. This does not appear to endanger the bridge at this time but it should be watched. See copy of Plan.

✓ 1st Lake:


1. The concrete on the upstream side of the dam under the Gate House and to the left of the Gate House has been repaired. This was done in November 1975.
2. Concrete at intake to the gates is eroded. This is <sup>under</sup> in the area where repairs were made last November. This area is where the emergency stoplogs would be placed so that work could be done on the gates.

3. There is an area between Southern abutment and southern spillway wall where the earth fill on the downstream side has failed. This area had failed some year back and the grass had re-established itself in the area. This area is protected by the spillway wall and the abutment both of which are founded on ledge. This area should be watched for any further developments. New England Power plans no work on this at this time. They plan to monitor any further development and re-evaluate the situation in a year or upon any changes.

4. The two piers under the gate house on the upstream side show signs of deterioration and should be checked next year.

5. Concrete on the upstream face of the logway has deteriorated since last year's inspection. This should be repaired in the near future.

SCB:L



REFERENCE DRAWINGS	
10-000000 Plan	10-000000 Plan
10-000000 Section	10-000000 Section
10-000000 Detail	10-000000 Detail
10-000000 Elevation	10-000000 Elevation
10-000000 Foundation	10-000000 Foundation
10-000000 Roof	10-000000 Roof
10-000000 Stairs	10-000000 Stairs
10-000000 Windows	10-000000 Windows
10-000000 Doors	10-000000 Doors
10-000000 Fences	10-000000 Fences
10-000000 Landscaping	10-000000 Landscaping
10-000000 Utilities	10-000000 Utilities
10-000000 Site Plan	10-000000 Site Plan
10-000000 Survey	10-000000 Survey
10-000000 Topography	10-000000 Topography
10-000000 Geology	10-000000 Geology
10-000000 Hydrology	10-000000 Hydrology
10-000000 Climatology	10-000000 Climatology
10-000000 Ecology	10-000000 Ecology
10-000000 Archaeology	10-000000 Archaeology
10-000000 Anthropology	10-000000 Anthropology
10-000000 Sociology	10-000000 Sociology
10-000000 Psychology	10-000000 Psychology
10-000000 Education	10-000000 Education
10-000000 Health	10-000000 Health
10-000000 Law	10-000000 Law
10-000000 Business	10-000000 Business
10-000000 Engineering	10-000000 Engineering
10-000000 Architecture	10-000000 Architecture
10-000000 Art	10-000000 Art
10-000000 Music	10-000000 Music
10-000000 Theater	10-000000 Theater
10-000000 Film	10-000000 Film
10-000000 Television	10-000000 Television
10-000000 Radio	10-000000 Radio
10-000000 Internet	10-000000 Internet
10-000000 Computing	10-000000 Computing
10-000000 Mathematics	10-000000 Mathematics
10-000000 Science	10-000000 Science
10-000000 History	10-000000 History
10-000000 Literature	10-000000 Literature
10-000000 Languages	10-000000 Languages
10-000000 Philosophy	10-000000 Philosophy
10-000000 Religion	10-000000 Religion
10-000000 Ethics	10-000000 Ethics
10-000000 Politics	10-000000 Politics
10-000000 Economics	10-000000 Economics
10-000000 Sociology	10-000000 Sociology
10-000000 Anthropology	10-000000 Anthropology
10-000000 Archaeology	10-000000 Archaeology
10-000000 Geography	10-000000 Geography
10-000000 Environmental Science	10-000000 Environmental Science
10-000000 Health Sciences	10-000000 Health Sciences
10-000000 Life Sciences	10-000000 Life Sciences
10-000000 Physical Sciences	10-000000 Physical Sciences
10-000000 Earth Sciences	10-000000 Earth Sciences
10-000000 Atmospheric Sciences	10-000000 Atmospheric Sciences
10-000000 Oceanography	10-000000 Oceanography
10-000000 Planetary Science	10-000000 Planetary Science
10-000000 Astronomy	10-000000 Astronomy
10-000000 Cosmology	10-000000 Cosmology
10-000000 Astrophysics	10-000000 Astrophysics
10-000000 Particle Physics	10-000000 Particle Physics
10-000000 Nuclear Physics	10-000000 Nuclear Physics
10-000000 Quantum Mechanics	10-000000 Quantum Mechanics
10-000000 Relativity	10-000000 Relativity
10-000000 Thermodynamics	10-000000 Thermodynamics
10-000000 Electromagnetism	10-000000 Electromagnetism
10-000000 Optics	10-000000 Optics
10-000000 Acoustics	10-000000 Acoustics
10-000000 Mechanics	10-000000 Mechanics
10-000000 Fluid Dynamics	10-000000 Fluid Dynamics
10-000000 Solid Mechanics	10-000000 Solid Mechanics
10-000000 Materials Science	10-000000 Materials Science
10-000000 Metallurgy	10-000000 Metallurgy
10-000000 Ceramics	10-000000 Ceramics
10-000000 Polymers	10-000000 Polymers
10-000000 Composites	10-000000 Composites
10-000000 Nanotechnology	10-000000 Nanotechnology
10-000000 Biotechnology	10-000000 Biotechnology
10-000000 Genetic Engineering	10-000000 Genetic Engineering
10-000000 Biochemistry	10-000000 Biochemistry
10-000000 Molecular Biology	10-000000 Molecular Biology
10-000000 Cell Biology	10-000000 Cell Biology
10-000000 Developmental Biology	10-000000 Developmental Biology
10-000000 Evolutionary Biology	10-000000 Evolutionary Biology
10-000000 Systematics	10-000000 Systematics
10-000000 Taxonomy	10-000000 Taxonomy
10-000000 Ecology	10-000000 Ecology
10-000000 Conservation Biology	10-000000 Conservation Biology
10-000000 Environmental Management	10-000000 Environmental Management
10-000000 Resource Management	10-000000 Resource Management
10-000000 Urban Planning	10-000000 Urban Planning
10-000000 Transportation Planning	10-000000 Transportation Planning
10-000000 Land Use Planning	10-000000 Land Use Planning
10-000000 Regional Planning	10-000000 Regional Planning
10-000000 International Development	10-000000 International Development
10-000000 Global Studies	10-000000 Global Studies
10-000000 Area Studies	10-000000 Area Studies
10-000000 Cultural Studies	10-000000 Cultural Studies
10-000000 Media Studies	1

NEW  
LAND POWER CONSTRUCTION CO.  
ENGINEERS & CONTRACTORS  
1000 15th St. N.E.  
Atlanta, Georgia 30309  
404-525-1100

SET PLANS

GENERAL LAYOUT


MAIN DAM

1st CONNECTicut LANE STORAGE

SECOND, THIRD & FOURTH QUARTERS  
SANDWICH WITH CONCRETE  
SANDWICH

DATE: 04-11-78  
BY: [illegible]

H-4549-2




ELEVATION, LOOKING NORTH




ELEVATION, LOOKING NORTH




1954-H



PLAN





PLAN SHOWING BOLTS









TYPICAL CROSS SECTIONS















TYPICAL SECTIONS THROUGH DAM






SLUICE GATES



LOCKWAY

THROUGH DAM



PLAN

REVISION OF MAR 10 1923

NEW ENGLAND POWER CONSTRUCTION CO.  
ENGINEERS & ARCHITECTS  
PART OF NEW ENGLAND POWER CO. SYSTEM  
BOSTON, MASS.  
CONSULTING ENGINEERS

FIRST CONNECTICUT LANE STORAGE  
MAIN DAM  
PLAN AND SECTIONS

H-4462

3a/3

APPENDIX C  
PHOTOGRAPHS


APPENDIX C

REPRESENTATIVE PHOTOGRAPHS OF PROJECT

<u>LOCATION PLAN</u>		<u>Page</u>
Plan 1 - Location of Photographs Taken June 28, 1978		C-3
<u>PHOTOGRAPHS</u>		
<u>No.</u>	<u>Negative No.</u>	<u>Page</u>
1. Upstream side of dam, showing flashboards and footbridge, looking south.	9-16A	C-4
2. Downstream side showing north bank and erosion of concrete facing.	10-13	C-4
3. Looking downstream over gate sluices, showing erosion of concrete curb.	10-11	C-5
4. Downstream face with one gate open, fish pipe flowing, and south abutment at right.	9-35A	C-5
5. Downstream face, showing concrete erosion at construction joints.	9-33A	C-6
6. South abutment, showing efflorescence in concrete.	10-8	C-6
7. North abutment on upstream side.	9-13A	C-7
8. North abutment on downstream side.	9-14A	C-7
9. Concrete piers near south abutment and downstream face of spillway.	10-10	C-8
10. Footbridge support at north abutment with timber flooring.	9-15A	C-8
11. New concrete piers for log way near south end of dam.	10-16	C-9

<u>No.</u>	<u>Negative No.</u>	<u>Page</u>
12. South abutment on the upstream side.	10-17	C-9
13. Upstream slope of south dike.	10-4	C-10
14. Downstream slope of south dike.	10-5	C-10
15. Erosion of south bank downstream. On the left: south abutment above, retaining wall below.	9-36A	C-11
16. Downstream channel is Connecticut River, looking from the footbridge.	10-3	C-11








1. Upstream side of dam, showing flashboards and footbridge, looking south.



2. Downstream side showing north bank and erosion of concrete facing.



3. Looking downstream over gate sluices, showing erosion of concrete curbs.



4. Downstream face with one gate open, fish pipe flowing, and south abutment at right.

5. Downstream face, showing  
concrete erosion at  
construction joints.



6. South abutment,  
showing efflorescence  
in concrete.



7. North abutment on upstream side.




8. North abutment on downstream side.

9. Concrete piers near south abutment and downstream face of spillway.




10. Footbridge support at north abutment with timber flooring.

11. New concrete piers  
for log way near  
south end of dam.



12. South abutment on the upstream side.




13. Upstream slope of south dike.



14. Downstream slope of south dike.



15. Erosion of south bank downstream. On the left; south abutment above, retaining wall below.



16. Downstream view of the river, looking from the footbridge.

APPENDIX D

HYDROLOGIC & HYDRAULIC COMPUTATIONS

SUBJECT MOUNTAIN LAKES DAM - PM  
SPILLWAY TEST LIKE DAM

conclude, in doing the spillway test flood hydrograph, the total drainage area of the First Connecticut Lake Dam was considered to be the area contributing runoff into the First Connecticut Lake for the lake of substructure analysis.

LA = 83.0 square miles

Soil Classification = Large

Regional Soil Classification = Low

Spillway Test Flood = 1/2 PMF TO PMF

Calculate PMF using "PMF Maximum Flood Estimation Maximum 1:1 Lake Exchange in Phase I Dam Safety Investigations, March 1977".

Use Mountain L.

$$1. \text{ PMF for First Connecticut Lake} = 83.0 \times 1247 \\ = 103,501 \text{ cfs}$$

$$2. \text{ Spillway Test Flood Peak Inflow} = 103,500 \text{ cfs}$$

PROJECT EN-16(1)

FILE NUMBER 5120

SHEET NUMBER 2

DATE 2-2-54

COMPUTED BY W.H.

CHECKED BY W.H.

SUBJECT PORT AND TIDE GAGE

SPILLWAY TEST FLOOD WELFARE VERIFICATION  
(BASED ON 335 DIMENSIONLESS UNIT HYDROGRAPH)

Length of Taper = 52,300'

Difference in Elevation = 1558'

$$T_c = \frac{(52,300)^{1.15}}{7700 \times (1558)^{2.43}}$$

$$= \frac{266,353.0}{7700 \times 16.2}$$

$$= 2.13 \quad \text{At } 2.0 \text{ sec.}$$

SUBJECT 11' T. SPILLWAY TEST FLOOD

DATE 11/1/55

COMPUTED BY W. L. R.

CHECKED BY

SPILLWAY TEST FLOOD PEAK INFLOW = 103500 CFS  
(BASED ON 60% DIMENSIONLESS UNIT HYDROGRAPH)

$$T_c = 2.0 \text{ hrs.}$$

SPILLWAY TEST FLOOD PEAK INFLOW = 103500 CFS

T (hrs.)	T/T <sub>c</sub>	Q/Q <sub>p</sub>	Q (CFS)
0.50	0.25	0.05	5175
1.00	0.50	0.18	18,630
1.50	0.75	0.72	75,556
2.00	1.00	1.00	103,500
2.50	1.25	0.80	80,801
3.00	1.50	0.40	41,760
3.50	1.75	0.25	25,875
4.00	2.00	0.17	17,595
5.50	2.75	0.06	6,210
7.00	3.50	0.02	2,070
8.00	4.00	0.01	1,025

PROJECT EN-006(1)

FILE NUMBER EN-006

SHEET NUMBER 4

SUBJECT INLET CONNECTION TAKE DAM

DATE 1/1/58

COMPOSITE DISCHARGE RATING TABLE

COMPUTED BY 1/1/58

CHECKED BY 1/1/58

REFER TO PAGES 5, 6, AND 7

ELEVATION	DISCHARGE	WEIR	SLUICE	CONCRETE	TOTAL
	THROUGH	WEIR	RATES		
	LEGWAY	LEGWAY	LEGWAY		
	CFS	CFS	CFS	CFS	
15.26.0	1830		3500	15	5330
15.26.5	1977		3500	15	5477
15.27.0	2115	1100	3500	15	5773
15.27.5	2254	1000	3500	15	7199
15.28.0	2311	3100	3500	15	9026
15.28.5	2400	4500	3500	15	10575
15.29.0	2531	5800	3500	16	12057
15.29.5	2677	7400	3500	16	13765
15.30.0	2752	8900	3500	16	15394

DISCHARGE RATING FOR LEGWAY:

Discharge through the legway

$$Q = C_d \cdot b \cdot H \cdot \sqrt{2g} = C_d \cdot b \cdot H \cdot \sqrt{2g} \cdot y_1^{3/2}$$





$$b = 10 \text{ ft}$$

$$\text{FAY } H = y_1, \quad b/y_1 = 1$$


$$\therefore C_d = 0.45 \text{ (RIDGE ENGINEER - ING HYDRAULICS PAGE 537)}$$

$$Q = 0.45 \times 10 \times \sqrt{2g} \cdot y_1^{3/2} \\ = 36.11 y_1^{3/2}$$

# FIRST CONNECTICUT LAKE SPILLWAY DISCHARGE RATINGS



Sheet 2 of 2





Sheet 1 of 2

DISCHARGE IN C.F.S.

0 100 200 300 400 500 600 700 800 900 1000 1100 1200 1300 1400 1500 1600 1700 1800 1900

HUNDREDS OF REVOLUTIONS OF COUNTER

1640 59 58 57 56 55 54 53 52 51 50 49 48 47 46 45 44 43 42 41 40 39 38 37 36 35 34 33 32 31 30 29 28 27 26 25 24 23 22 21 20 19 18 17 16 15 14 13 12 11 10 9 8 7 6 5 4 3 2 1

POND WATER SURFACE ELEVATION - C.F.S. DATUM

Fish Pipe  
C.F.S. Elev.

6 1611  
7 1613  
8 1615  
9 1613  
10 1622  
11 1626  
12 1630  
13 1633  
14 1636  
15 1638  
16 1640  
17

FIRST CONNECTICUT LAKE  
DISCHARGE RATING  
OF ONE OF TWO SLUICES

Based on Current Meter Measurements  
of Sept. 15-20, 1941. Curve #258 063043 ARG.

N.E.P.S. CO. 2-11-47 G.M.B.

FAY SPOFFORD & THORNDIKE INC.  
ENGINEERS  
BOSTON

PROJECT EN-11111

SHEET NUMBER EN-006

SUBJECT FIRST CONVENTION LANE LHM

DATE 2/1/57

STORAGE CAP. IN ACRES ELEV. 636

COMPUTED BY W. H. H.

CHECKED BY W. H. H.

ELEVATION	STORAGE ABOVE ELEV. 1610 ACRES-FT	STORAGE ABOVE ELEV. 1636 ACRES-FT	STORAGE ABOVE ELEV. 1636 FT <sup>3</sup>
16260	64,272	0	0
16265	65,770	14,97	65.21 x 10 <sup>6</sup>
16270	67,276	3,003	130.21 x 10 <sup>6</sup>
16275	68,790	4,517	196.76 x 10 <sup>6</sup>
16280	70,314	6,041	262.15 x 10 <sup>6</sup>
16285	71,845	7,572	329.24 x 10 <sup>6</sup>
16290	73,386	9,113	396.46 x 10 <sup>6</sup>
16295	74,925	10,662	464.44 x 10 <sup>6</sup>
16300	76,473	12,220	532.20 x 10 <sup>6</sup>

REFER TO TABLE ON PAGES 9 TO 14

FIRST CONNECTICUT LAKE  
Storage Above Elevation 1610.

Sheet 1 of 6  
D.A.=83.0 Sq.Mi.

U.S.O.S. Elev.	Acres	Acres- Feet	C.F.S. Days	Inches on 37.6 Sq.Mi.	Sq.Mi.	Million Cub.Ft.
1610.0	1670	187	91	.093	.042	8.2
.1	1676	187	91	.093	.042	8.2
.2	1882	375	189	.187	.085	16.4
.3	1888	561	281	.281	.127	24.6
.4	1894	753	382	.376	.170	32.8
.5	1900	942	472	.470	.213	41.1
.6	1906	1133	572	.565	.256	49.4
.7	1912	1324	668	.660	.299	57.7
.8	1918	1515	761	.756	.342	66.0
.9	1924	1707	861	.852	.386	74.4
1611.0	1930	1893	958	.948	.429	82.8
.1	1936	2083	1055	1.044	.473	91.2
.2	1941	2287	1153	1.141	.517	99.6
.3	1946	2482	1251	1.238	.561	108.1
.4	1952	2677	1349	1.335	.605	116.6
.5	1958	2872	1446	1.432	.649	125.1
.6	1963	3068	1547	1.530	.693	133.6
.7	1968	3265	1646	1.628	.737	142.2
.8	1974	3462	1745	1.726	.782	150.8
.9	1980	3659	1845	1.825	.827	159.4
1612.0	1985	3857	1945	1.924	.872	168.0
.1	1990	4056	2045	2.023	.916	176.7
.2	1995	4256	2145	2.122	.961	185.4
.3	2000	4456	2246	2.222	1.006	194.1
.4	2005	4656	2347	2.322	1.052	202.8
.5	2010	4856	2446	2.422	1.097	211.5
.6	2015	5058	2550	2.522	1.143	220.3
.7	2020	5260	2652	2.623	1.188	229.1
.8	2025	5462	2754	2.724	1.234	237.9
.9	2030	5664	2856	2.825	1.279	246.7
1613.0	2035	5865	2956	2.926	1.325	255.5
.1	2040	6072	3061	3.028	1.371	264.5
.2	2045	6276	3164	3.130	1.418	273.4
.3	2050	6480	3267	3.232	1.464	282.3
.4	2055	6686	3371	3.334	1.510	291.2
.5	2060	6892	3475	3.437	1.557	300.2
.6	2065	7098	3579	3.540	1.603	309.2
.7	2070	7304	3683	3.643	1.650	318.2
.8	2075	7512	3787	3.746	1.697	327.2
.9	2080	7720	3892	3.849	1.744	336.3
1614.0	2085	7928	3995	3.953	1.791	345.3
.1	2090	8136	4102	4.057	1.838	354.4
.2	2095	8346	4208	4.162	1.885	363.5
.3	2100	8556	4314	4.267	1.933	372.7
.4	2105	8766	4420	4.372	1.980	381.8
.5	2110	8976	4526	4.477	2.027	391.0
.6	2115	9186	4632	4.582	2.076	400.2
.7	2120	9397	4739	4.687	2.123	409.4
.8	2125	9608	4846	4.793	2.171	418.7
.9	2130	9819	4953	4.899	2.219	427.9
1615.0	9925	10027	5061	5.004	2.267	437.3

FIRST CONNECTICUT LAKE  
Storage Above Elevation 1610.Sheet 2 of 6  
D.A. #83.0 Sq.Mi.

U.S.O.S. Elev.	Acres	Acra- Feet	C.F.S. Days	Inches on		Million Cub.Ft.
				37.6 Sq.Mi.	83.0 Sq.Mi.	
1615.0	2148	10,611	5181	5.112	2.316	445.3
.1	2140	10,251	5189	5.112	2.316	445.3
.2	2145	10,465	5277	5.219	2.361	455.9
.3	2150	10,680	5385	5.326	2.413	465.2
.4	2155	10,826	5493	5.434	2.461	475.6
.5	2160	11,111	5601	5.541	2.513	485.3
.6	2165	11,328	5711	5.647	2.569	495.4
.7	2170	11,544	5820	5.757	2.628	505.9
.8	2175	11,761	5930	5.866	2.687	515.3
.9	2180	11,979	6040	5.974	2.745	521.8
1616.0	2181	12,197	6150	6.083	2.803	531.3
.1	2190	12,417	6260	6.192	2.861	541.9
.2	2194	12,636	6371	6.302	2.921	550.4
.3	2199	12,855	6481	6.411	2.974	560.0
.4	2203	13,075	6592	6.521	3.031	569.6
.5	2205	13,296	6703	6.631	3.084	577.2
.6	2212	13,517	6815	6.741	3.133	585.8
.7	2217	13,738	6927	6.851	3.183	593.4
.8	2221	13,960	7039	6.962	3.234	602.1
.9	2226	14,182	7151	7.073	3.284	617.8
1617.0	2230	14,405	7263	7.184	3.334	627.5
.1	2235	14,629	7376	7.295	3.385	637.2
.2	2239	14,852	7489	7.407	3.435	647.0
.3	2244	15,076	7602	7.519	3.486	656.7
.4	2248	15,301	7715	7.631	3.536	666.5
.5	2253	15,526	7828	7.743	3.587	676.3
.6	2257	15,752	7942	7.856	3.638	686.1
.7	2262	15,978	8056	7.968	3.689	696.0
.8	2266	16,204	8170	8.081	3.660	705.8
.9	2271	16,431	8284	8.194	3.712	715.7
1618.0	2275	16,658	8399	8.307	3.763	725.6
.1	2280	16,886	8514	8.421	3.815	735.5
.2	2284	17,114	8629	8.535	3.866	745.5
.3	2289	17,343	8744	8.649	3.918	755.4
.4	2293	17,572	8860	8.763	3.970	765.4
.5	2298	17,801	8975	8.877	4.021	775.4
.6	2302	18,031	9091	8.992	4.073	785.4
.7	2307	18,262	9208	9.107	4.125	795.5
.8	2311	18,493	9324	9.222	4.178	805.5
.9	2316	18,724	9441	9.338	4.230	815.6
1619.0	2320	18,956	9557	9.453	4.282	825.7
.1	2324	19,188	9675	9.569	4.335	835.8
.2	2329	19,421	9792	9.685	4.387	846.0
.3	2334	19,654	9909	9.801	4.440	856.1
.4	2338	19,888	10,027	9.918	4.493	866.3
.5	2343	20,122	10,145	10,036	4.545	876.5
.6	2347	20,356	10,264	10,153	4.598	886.7
.7	2352	20,591	10,382	10,269	4.652	896.9
.8	2356	20,826	10,501	10,386	4.705	907.2
.9	2361	21,062	10,620	10,504	4.758	917.5
1620.0	2365	21,297	10,739	10,622	4.811	927.8

FIRST CONNECTICUT LAKE  
Storage Above Elevation 1610.

Sheet 3 of 6  
D.A. - 83.0 Sq.Mi.

U.S.O.S.	Acres	Acres- Foot	C.F.S. Days	Inches on		Million Cub. Ft.
				37.6 Sq.Mi.	63.0 Sq.Mi.	
1620.0	2365	21,899	10,749	10,742	4.811	927.8
.1	2370	21,935	10,759	10,750	4.815	936.1
.2	2374	21,772	10,978	10,858	4.918	948.4
.3	2379	22,010	11,098	10,976	4.972	958.8
.4	2383	22,248	11,218	11,095	5.026	969.1
.5	2387	22,487	11,338	11,214	5.080	979.5
.6	2392	22,726	11,458	11,333	5.134	989.9
.7	2397	22,965	11,579	11,453	5.188	1000.4
.8	2401	23,205	11,700	11,573	5.242	1010.8
.9	2406	23,446	11,821	11,693	5.296	1021.3
1621.0	2410	23,687	11,941	11,813	5.350	1031.8
.1	2414	23,928	12,061	11,933	5.405	1042.3
.2	2418	24,169	12,186	12,053	5.460	1052.8
.3	2422	24,411	12,308	12,174	5.514	1063.3
.4	2426	24,654	12,430	12,295	5.569	1073.9
.5	2430	24,895	12,553	12,416	5.623	1084.5
.6	2434	25,140	12,675	12,537	5.679	1095.1
.7	2438	25,383	12,798	12,659	5.734	1105.7
.8	2442	25,627	12,921	12,780	5.789	1116.3
.9	2446	25,872	13,044	12,902	5.844	1127.0
1622.0	2450	26,116	13,166	13,024	5.899	1137.6
.1	2454	26,362	13,291	13,147	5.955	1148.3
.2	2458	26,607	13,415	13,269	6.011	1159.0
.3	2462	26,853	13,539	13,392	6.066	1169.7
.4	2466	27,100	13,664	13,515	6.122	1180.5
.5	2470	27,347	13,788	13,638	6.177	1191.2
.6	2474	27,594	13,913	13,761	6.233	1202.0
.7	2478	27,841	14,038	13,884	6.289	1212.8
.8	2482	28,089	14,163	14,008	6.345	1223.6
.9	2486	28,338	14,288	14,132	6.402	1234.4
1623.0	2490	28,587	14,413	14,255	6.458	1245.2
.1	2494	28,835	14,539	14,379	6.514	1256.1
.2	2498	29,083	14,665	14,505	6.570	1266.9
.3	2502	29,335	14,791	14,629	6.627	1277.8
.4	2506	29,586	14,917	14,754	6.683	1288.7
.5	2510	29,837	15,043	14,879	6.739	1299.7
.6	2514	30,088	15,170	15,005	6.795	1310.6
.7	2518	30,339	15,297	15,130	6.851	1321.6
.8	2522	30,591	15,424	15,256	6.911	1332.5
.9	2526	30,844	15,551	15,382	6.968	1343.5
1624.0	2530	31,097	15,679	15,507	7.025	1354.6
.1	2534	31,350	15,805	15,634	7.082	1365.6
.2	2538	31,603	15,934	15,760	7.139	1376.6
.3	2542	31,857	16,062	15,887	7.196	1387.7
.4	2546	32,112	16,191	16,014	7.253	1398.8
.5	2550	32,367	16,319	16,141	7.310	1409.9
.6	2554	32,622	16,448	16,268	7.367	1421.0
.7	2558	32,877	16,577	16,396	7.424	1432.1
.8	2562	33,133	16,706	16,523	7.481	1443.3
.9	2566	33,389	16,835	16,651	7.538	1454.4
1625.0	2570	33,645	16,964	16,779	7.595	1465.6

FIRST CONNECTICUT LAKE  
Storage Above Elevation 1610.

Sheet 4 of 6  
D.A. - 83.0 Sq.Mi.

U.S.O.S. Elev.	Acres	Acre- Feet	C.F.S. Days	Inches on		Million Cub.Ft.
				37.6 Sq.Mi.	83.0 Sq.Mi.	
1625.0	2570	33,115	17,521	16.779	7.431	1445.6
.1	2574	33,734	17,521	16.958	7.659	1476.8
.2	2578	34,161	17,224	17.036	7.717	1468.1
.3	2582	34,419	17,354	17.165	7.775	1499.3
.4	2586	34,678	17,484	17.294	7.834	1510.6
.5	2590	34,937	17,613	17.423	7.892	1521.8
.6	2594	35,196	17,743	17.552	7.951	1533.1
.7	2598	35,455	17,872	17.681	8.009	1544.4
.8	2602	35,715	18,002	17.811	8.068	1555.7
.9	2606	35,976	18,132	17.941	8.127	1567.1
1626.0	2610	36,237	18,261	18.071	8.185	1578.5
.1	2614	36,498	18,392	18.202	8.245	1589.8
.2	2618	36,759	18,524	18.332	8.304	1601.2
.3	2622	37,021	18,656	18.463	8.363	1612.6
.4	2626	37,284	18,788	18.594	8.422	1624.1
.5	2630	37,547	18,921	18.725	8.482	1635.5
.6	2634	37,810	19,054	18.856	8.541	1647.0
.7	2638	38,073	19,187	18.987	8.601	1658.5
.8	2642	38,337	19,330	19.119	8.660	1670.0
.9	2646	38,602	19,463	19.251	8.720	1681.5
1627.0	2650	38,867	19,598	19.383	8.780	1693.0
.1	2654	39,132	19,730	19.515	8.840	1704.6
.2	2658	39,397	19,864	19.647	8.900	1716.1
.3	2662	39,663	19,998	19.780	8.960	1727.7
.4	2666	39,929	20,132	19.913	9.020	1739.3
.5	2670	40,196	20,267	20.046	9.080	1751.0
.6	2674	40,464	20,402	20.179	9.141	1762.6
.7	2678	40,732	20,537	20.313	9.201	1774.2
.8	2682	41,000	20,672	20.447	9.262	1785.9
.9	2686	41,268	20,807	20.580	9.322	1797.6
1628.0	2690	41,537	20,943	20.714	9.383	1809.3
.1	2694	41,805	21,078	20.849	9.444	1821.0
.2	2698	42,075	21,214	20.983	9.505	1832.8
.3	2702	42,345	21,350	21.117	9.566	1844.6
.4	2706	42,616	21,487	21.252	9.627	1856.3
.5	2710	42,887	21,623	21.386	9.688	1868.1
.6	2714	43,158	21,760	21.521	9.749	1879.9
.7	2718	43,429	21,897	21.658	9.811	1891.8
.8	2722	43,701	22,034	21.794	9.872	1903.6
.9	2726	43,974	22,171	21.930	9.934	1915.5
1629.0	2730	44,247	22,308	22.067	9.995	1927.4
.1	2734	44,520	22,447	22.203	10.057	1939.3
.2	2738	44,793	22,585	22.338	10.119	1951.2
.3	2742	45,067	22,723	22.475	10.181	1963.1
.4	2746	45,342	22,861	22.612	10.243	1975.1
.5	2750	45,617	23,000	22.749	10.305	1987.0
.6	2754	45,892	23,138	22.886	10.367	1999.0
.7	2758	46,167	23,277	23.023	10.429	2011.0
.8	2762	46,443	23,417	23.161	10.491	2023.1
.9	2766	46,720	23,556	23.299	10.554	2035.1
1630.0	2770	47,000	23,695	23.437	10.616	2047.2

FIRST CONNECTION LINE Sheet 5 of 6  
Storage Above Elevation 1610. D.A. - 83.0 Sq.Mi.

U.S.G.S. Elev.	Acres	Acre- feet	C.F.S. Days	Inches on		Million Cub. Ft.
				37.6 Sq.Mi.	83.0 Sq.Mi.	
1630.0	2770	47,556	23,655	23,655	10,746	2177.2
.1	2774	47,551	23,655	23,655	10,749	2177.2
.2	2778	47,551	23,655	23,714	10,742	2171.3
.3	2782	47,822	24,115	23,852	10,805	2183.4
.4	2786	48,103	24,256	23,921	10,868	2195.6
.5	2790	48,387	24,395	24,130	10,931	2197.7
.6	2794	48,665	24,537	24,270	10,994	2119.9
.7	2798	48,945	24,678	24,409	11,057	2132.0
.8	2802	49,225	24,819	24,549	11,120	2144.2
.9	2806	49,505	24,961	24,689	11,183	2156.5
1631.0	2810	50,000	25,117	24,752	11,247	2168.7
.1	2814	50,000	25,234	24,909	11,310	2180.9
.2	2817	50,349	25,385	25,109	11,374	2193.2
.3	2820	50,631	25,528	25,250	11,438	2205.5
.4	2824	50,913	25,670	25,392	11,501	2217.8
.5	2828	51,195	25,813	25,531	11,565	2230.1
.6	2831	51,479	25,956	25,673	11,629	2242.4
.7	2834	51,762	26,098	25,814	11,693	2254.7
.8	2838	52,046	26,241	25,955	11,757	2267.1
.9	2842	52,330	26,385	26,097	11,821	2279.5
1632.0	2846	52,614	26,527	26,239	11,885	2291.9
.1	2850	52,899	26,671	26,381	11,949	2304.3
.2	2852	53,184	26,815	26,523	12,014	2316.7
.3	2855	53,469	26,959	26,665	12,079	2329.1
.4	2859	53,755	27,103	26,808	12,143	2341.5
.5	2863	54,041	27,247	26,950	12,208	2354.0
.6	2866	54,327	27,392	27,093	12,272	2366.5
.7	2869	54,614	27,536	27,236	12,337	2379.0
.8	2873	54,901	27,681	27,379	12,402	2391.5
.9	2876	55,188	27,826	27,522	12,467	2404.0
1633.0	2880	55,475	27,971	27,665	12,532	2416.5
.1	2884	55,761	28,115	27,808	12,597	2429.1
.2	2887	56,048	28,261	27,951	12,662	2441.7
.3	2890	56,335	28,407	28,094	12,728	2454.2
.4	2894	56,621	28,553	28,237	12,793	2466.8
.5	2898	56,908	28,699	28,380	12,858	2479.3
.6	2901	57,195	28,846	28,523	12,923	2491.9
.7	2904	57,501	28,992	28,666	12,989	2504.4
.8	2908	57,791	29,138	28,810	13,055	2517.0
.9	2912	58,082	29,285	28,953	13,121	2529.5
1634.0	2916	58,375	29,431	29,097	13,187	2542.0
.1	2919	58,668	29,579	29,240	13,253	2554.5
.2	2922	58,961	29,726	29,383	13,318	2567.0
.3	2926	59,250	29,874	29,526	13,385	2579.5
.4	2929	59,543	30,021	29,669	13,451	2592.0
.5	2933	59,837	30,169	29,812	13,517	2604.5
.6	2936	60,130	30,317	29,955	13,583	2617.0
.7	2939	60,423	30,465	30,098	13,650	2629.5
.8	2943	60,717	30,613	30,240	13,716	2642.0
.9	2946	61,011	30,762	30,383	13,782	2654.5
1635.0	2950	61,305	30,910	30,526	13,849	2667.0

FIRST CONNECTICUT LAKE  
Storage Above Elevation 1610

Sheet 6 of 6  
D.A.=83.0 Sq.Mi.

U.S.O.S. Elev.	Acres	Acre- feet	C.F.S. Days	Inches on		Million Cub. Ft.
				37.6 Sq.Mi.	83.0 Sq.Mi.	
1635.0	2953	61,771	31,208	31.720	13.716	2693.3
.1	2953	61,771	31,208	31.720	13.716	2693.3
.2	2957	61,997	31,208	31.720	13.716	2695.2
.3	2960	62,193	31,357	31.915	14.042	2707.1
.4	2964	62,452	31,507	31.193	14.126	2722.0
.5	2967	62,652	31,507	31.193	14.126	2724.9
.6	2971	63,001	31,507	31.193	14.126	2727.9
.7	2975	63,272	31,356	31.697	14.317	2730.8
.8	2978	63,677	32,125	31.755	14.385	2773.8
.9	2981	63,228	32,215	31.754	14.385	2766.8
1636.0	2982	63,228	32,215	31.754	14.385	2766.8
.1	2987	64,072	32,257	32.232	14.587	2812.6
.2	2992	64,871	32,708	32.351	14.654	2825.8
.3	2995	65,170	32,859	32.500	14.722	2838.8
.4	2999	65,170	32,215	32.400	14.722	2851.9
.5	3003	65,000	33,313	32.100	14.827	2853.0
.6	3005	65,071	33,313	32.250	14.923	2878.0
.7	3009	65,371	33,164	33.100	14.973	2891.1
.8	3013	65,673	33,616	33.250	15.061	2904.3
.9	3017	65,274	33,268	33.100	15.122	2917.4
1637.0	3019	65,274	33,268	33.100	15.122	2917.4
.1	3024	67,578	34,073	33.701	15.266	2943.7
.2	3027	67,881	34,225	33.852	15.334	2956.9
.3	3031	68,184	34,378	34.003	15.403	2970.1
.4	3034	68,487	34,531	34.154	15.471	2983.3
.5	3038	68,790	34,684	34.305	15.540	2996.5
.6	3041	69,093	34,837	34.457	15.608	3009.7
.7	3045	69,399	34,991	34.609	15.677	3023.0
.8	3048	69,703	35,144	34.761	15.746	3036.3
.9	3051	70,006	35,298	34.913	15.815	3049.6
1638.0	3053	70,006	35,298	34.913	15.815	3049.6
.1	3056	70,312	35,450	35.065	15.883	3062.8
.2	3062	70,925	35,760	35.370	16.032	3089.5
.3	3065	71,222	35,915	35.523	16.091	3102.8
.4	3069	71,528	36,070	35.675	16.160	3116.2
.5	3072	71,834	36,225	35.828	16.228	3129.5
.6	3076	72,140	36,379	35.980	16.297	3142.8
.7	3079	72,446	36,535	36.135	16.365	3156.1
.8	3083	72,752	36,690	36.290	16.433	3169.4
.9	3086	73,057	36,845	36.443	16.502	3182.7
1639.0	3088	73,057	36,845	36.443	16.502	3182.7
.1	3093	73,363	37,000	36.595	16.570	3196.0
.2	3097	73,669	37,155	36.748	16.638	3209.3
.3	3100	73,974	37,310	36.900	16.707	3222.6
.4	3104	74,279	37,465	37.053	16.775	3235.9
.5	3107	74,584	37,620	37.205	16.844	3249.2
.6	3111	74,889	37,775	37.358	16.912	3262.5
.7	3114	75,194	38,030	37.510	17.080	3291.3
.8	3118	75,499	38,285	37.663	17.148	3304.6
.9	3121	75,804	38,540	37.815	17.217	3317.9
1640.0	3123	75,804	38,540	37.815	17.217	3317.9



SUBJECT FIRST CONNECTICUT LAKE DAM  
FLOOD ROUTING COMPUTATIONS


DATE \_\_\_\_\_  
COMPUTED BY \_\_\_\_\_  
CHECKED BY \_\_\_\_\_

TIME	IN	OUT	Q	STORAGE	TIME	STORAGE
5.00	5407	5401	9.73X10 <sup>6</sup>	5.22X10 <sup>6</sup>	5.22	5.22
5.05	5407	5400	9.91X10 <sup>6</sup>	11.51X10 <sup>6</sup>	11.51	12.21
5.10	5407	5400	10.60X10 <sup>6</sup>	73.71X10 <sup>6</sup>	83.22X10 <sup>6</sup>	16.35
5.15	5407	5400	13.22X10 <sup>6</sup>	132.81X10 <sup>6</sup>	146.03X10 <sup>6</sup>	16.37
5.20	5407	5400	17.51X10 <sup>6</sup>	17.51X10 <sup>6</sup>	17.51X10 <sup>6</sup>	16.38
5.25	5407	5400	22.11X10 <sup>6</sup>	22.11X10 <sup>6</sup>	22.11X10 <sup>6</sup>	16.39
5.30	5407	5400	26.11X10 <sup>6</sup>	26.11X10 <sup>6</sup>	26.11X10 <sup>6</sup>	16.40
5.35	5407	5400	29.11X10 <sup>6</sup>	29.11X10 <sup>6</sup>	29.11X10 <sup>6</sup>	16.41
5.40	5407	5400	31.11X10 <sup>6</sup>	31.11X10 <sup>6</sup>	31.11X10 <sup>6</sup>	16.42
5.45	5407	5400	32.11X10 <sup>6</sup>	32.11X10 <sup>6</sup>	32.11X10 <sup>6</sup>	16.43
5.50	5407	5400	32.11X10 <sup>6</sup>	32.11X10 <sup>6</sup>	32.11X10 <sup>6</sup>	16.44
5.55	5407	5400	31.11X10 <sup>6</sup>	31.11X10 <sup>6</sup>	31.11X10 <sup>6</sup>	16.45
6.00	5407	5400	29.11X10 <sup>6</sup>	29.11X10 <sup>6</sup>	29.11X10 <sup>6</sup>	16.46
6.05	5407	5400	26.11X10 <sup>6</sup>	26.11X10 <sup>6</sup>	26.11X10 <sup>6</sup>	16.47
6.10	5407	5400	22.11X10 <sup>6</sup>	22.11X10 <sup>6</sup>	22.11X10 <sup>6</sup>	16.48
6.15	5407	5400	17.51X10 <sup>6</sup>	17.51X10 <sup>6</sup>	17.51X10 <sup>6</sup>	16.49
6.20	5407	5400	13.22X10 <sup>6</sup>	13.22X10 <sup>6</sup>	13.22X10 <sup>6</sup>	16.50
6.25	5407	5400	9.91X10 <sup>6</sup>	9.91X10 <sup>6</sup>	9.91X10 <sup>6</sup>	16.51
6.30	5407	5400	6.60X10 <sup>6</sup>	6.60X10 <sup>6</sup>	6.60X10 <sup>6</sup>	16.52
6.35	5407	5400	3.30X10 <sup>6</sup>	3.30X10 <sup>6</sup>	3.30X10 <sup>6</sup>	16.53
6.40	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.54
6.45	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.55
6.50	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.56
6.55	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.57
7.00	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.58
7.05	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.59
7.10	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.60
7.15	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.61
7.20	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.62
7.25	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.63
7.30	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.64
7.35	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.65
7.40	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.66
7.45	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.67
7.50	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.68
7.55	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.69
8.00	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.70
8.05	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.71
8.10	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.72
8.15	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.73
8.20	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.74
8.25	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.75
8.30	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.76
8.35	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.77
8.40	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.78
8.45	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.79
8.50	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.80
8.55	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.81
9.00	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.82
9.05	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.83
9.10	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.84
9.15	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.85
9.20	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.86
9.25	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.87
9.30	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.88
9.35	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.89
9.40	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.90
9.45	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.91
9.50	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.92
9.55	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.93
10.00	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.94
10.05	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.95
10.10	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.96
10.15	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.97
10.20	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.98
10.25	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	16.99
10.30	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.00
10.35	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.01
10.40	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.02
10.45	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.03
10.50	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.04
10.55	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.05
11.00	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.06
11.05	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.07
11.10	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.08
11.15	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.09
11.20	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.10
11.25	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.11
11.30	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.12
11.35	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.13
11.40	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.14
11.45	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.15
11.50	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.16
11.55	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.17
12.00	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.18
12.05	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.19
12.10	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.20
12.15	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.21
12.20	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.22
12.25	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.23
12.30	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.24
12.35	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.25
12.40	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.26
12.45	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.27
12.50	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.28
12.55	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.29
13.00	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.30
13.05	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.31
13.10	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.32
13.15	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.33
13.20	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.34
13.25	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.35
13.30	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.36
13.35	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.37
13.40	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.38
13.45	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.39
13.50	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.40
13.55	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.41
14.00	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.42
14.05	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.43
14.10	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.44
14.15	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.45
14.20	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.46
14.25	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.47
14.30	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.48
14.35	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.49
14.40	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.50
14.45	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.51
14.50	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.52
14.55	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.53
15.00	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.54
15.05	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	17.55
15.10	5407	5400	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	0.00X10 <sup>6</sup>	1

MASSACHUSETTS DEPARTMENT OF  
PUBLIC WORKS  
DIVISION OF DAMS  
100 WATER STREET  
BOSTON, MASS.  
MASSACHUSETTS DEPARTMENT OF  
PUBLIC WORKS  
DIVISION OF DAMS  
100 WATER STREET  
BOSTON, MASS.

# FIRST CONNECTICUT LAKE DAM

DATE: 1911  
BY: J. W. HARRIS  
CHECKED: J. W. HARRIS  
APPROVED: J. W. HARRIS



AD-A156 424


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAM  
FIRST CONNECTICUT LAKE. (U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV MAY 79

2/2


UNCLASSIFIED

F/G 13/13 NL





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A



# STORAGE CAPACITY - ELEVATION CURVE

106.5 (LOCAL DATUM) = 825 USGS (ESTIMATED)

FAY, SPOFFORD & THORNDIKE, INC.  
ENGINEERS  
BOSTON, MASS.

U.S. ARMY ENGINEER CORPS NEW ENGLAND DISTRICT  
CORPS OF ENGINEERS  
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS


## FIRST CONNECTICUT LAKE DAM

CONNECTICUT RIVER

SCALE 25 SHOWN

DATE AUGUST 1978

E-17



RATING CURVE FOR SPILLWAY AND DAM

106.5 (LOCAL DATUM) = 925 USGS (ESTIMATED)

FAY, SPOFFORD & THORNDIKE, INC.  
ENGINEERS  
BOSTON, MASS.


U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

# FIRST CONNECTICUT LAKE DAM

CONNECTICUT RIVER		NEW HAMPSHIRE	
SCALE	AS SHOWN	SCALE	AS SHOWN
DATE	AUGUST, 1978	DATE	AUGUST, 1978

Date



NEW HAMPSHIRE-VERMONT  
INDIAN STREAM QUADRANGLE 1925

SCALE 1:62500 (ACTUAL)

UNITED STATES  
GEOLOGICAL SURVEY





APPENDIX E

INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS

# INVENTORY OF DAMS IN THE UNITED STATES

ALL RIGHTS RESERVED	STATE	COUNTY	USL	CORP	NAME	LATITUDE (NORTH)	LONGITUDE (WEST)	REPORT DATE
100	000	000	000	000	FIRST CONNECTICUT LAKE DAM	4505.3	7117.5	00 SEP 70

POPULAR NAME		NAME OF IMPROVEMENT	
FIRST CONNECTICUT LAKE		FIRST CONNECTICUT LAKE	
RIVER OR STREAM	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	DIST FROM DAM (MI)	POPULATION
CONNECTICUT RIVER	PITTSBURG	8	726

TYPE OF DAM	YEAR COMPLETED	PURPOSES	HYDROPOWER CAPACITIES		DIST DOWN	FED R	PRV/FED	SCR	A	VEN/DATE
			INSTALLED (KW)	PRODUCED (KW)						
RECIPRO	1930	SCR	56	46	114000	91000	N	N	N	135LP/0

REMARKS	

D/S	SPILLWAY	MAXIMUM DISCHARGE (CFS)	VOLUME OF DAM (CFS)	POWER CAPACITY (KW)	INSTALLED (KW)	PRODUCED (KW)	NAVIGATION LOCKS	
							NO	YES
1	1120 C	55H	15000					

OWNER	ENGINEERING BY	CONSTRUCTION BY
NEW ENGLAND POWER CO	OWNER	OWNER

REGULATORY AGENCY	
DESIGN	CONSTRUCTION
NH WATER RES BD	NH WATER RES BD

INSPECTION BY	INSPECTION DATE	AUTHORITY FOR INSPECTION
FAY SPOFFORD + THORNDIKE, INC.	28 JUN 70	PL 92-567

REMARKS	

**END**

**FILMED**

**8-85**

**DTIC**